



KYCR COIL INDUSTRIES LTD.
S T E E L D I V I S I O N

255 Nasirabad Industrial Area, Chittagong, Bangladesh
Tel 880 31 681240-4 fax 880 31 628263, 651038
e m a i l i n f o @ k d s g r o u p . n e t

TO WHOM IT MAY CONCERN

This is to certify that M/s. Associated Builders Corporation Limited, ABC House, 8, Banani C/A, Kemal Ataturk Avenue, Dhaka- 1213 carried out Construction of KYCR Cold Rolled Building Complex at Barakumira, Chittagong. The details are furnished below :-

1. Date of Work Order : 28.08.2000
2. Date of Commencement : 28.08.2000
3. Scope of Works:
 - A. R.C.C Bored Piles of diameter 450 mm, lengths varying from 9.00 metre to 14.50 metre, 960 nos. costing Tk. 10.64 million for different structures.
 - B. Two (two level) basements (11.00 metre below ground level) costing TK. 100 (hundred) million (approx.) of the main Mill Building.
 - C. Water Complex Building.
 - D. 3 (three) Storied ECR Building including one two level basement.
 - E. Laboratory Building.
 - F. Electrical Control Building for Pickling Line.
 - G. Electrical Control Building for Edge Trimming Line.
 - H. Boiler Building.
 - I. Fume Scrubber Building.
 - J. Office Building.
4. Items of Works :
 - (i) Earth work : 55,400 Cum.
 - (ii) Sand Filling work : 56,700 Cum.
 - (iii) Sheet Piling Work : 1,550 Sqm.
 - (iv) Cement Concrete work : 5,761 Cum.
 - (v) R. C. C. work : 17,351 Cum.





KYCR COIL INDUSTRIES LTD.

S T E E L D I V I S I O N

255 Nasirabad Industrial Area, Chittagong, Bangladesh

Tel 880 31 681240-4 fax 880 31 682826,681398

e m a i l i n f o @ k d s g r o u p . n e t

- (vi) Reinforcement work : 1,420 Tons
- (vii) Shuttering work : 34,900 Sqm.
- (v) Steel Structure work including fabrication and erection with heavy cranes : 1,511 Tons
5. Total floor area :
- a) Main Mill Building, Pickling etc. : 9,950 Sqm.
- b) Other ancillary Buildings : 5,900 Sqm.
- c) Basement Area : 3,500 Sqm

6. Monthly /Annual production rates of key construction activities:

SL. NO.	Name of work	Monthly Production	Annual Production
a.	Earth Work.	7,528 Cum	57,684 Cum
b.	Reinforced Cement Concrete Work	2,264 Cum	17,351 Cum
c.	Fabrication and Erection of Steel Structures	260.00 Tons	1,511 Tons
7.	Total Cost	:	Tk. 341.62 million
8.	Date of Completion	:	31.07.2001

All works were successfully completed within the scheduled date. Their performance in respect of quality, methodology and construction management is highly satisfactory.

03.05.03

(MD. ABDUL HAKIM.)
SR. CIVIL ENGINEER.

KYCR COIL INDS. LTD.

